

1-a-y  
13-6-16

29

513

Icebreaker "J.D.Hazen".

Launched 15 May/16

	Ft.	Teeths.
Length from fore part of stem under the bowsprit to the left side of the head of the stern post	275	-
Length overall	292	-
Length at quarter of depth from top of weather deck at side amidships to bottom of keel.	275	-
Main breadth to outside of plank	57	88
Depth in hold from tonnage deck to ceiling at midships	21	9
Depth in hold from upper deck to ceiling at amidships in the case of three decks and upwards	40	85
Depth from top of beam amidships to top of keel.	25	15
Depth from top of deck at side amidships to bottom of keel	25	3
Round of beam.	1	2
Length of engine room.	87	5
Number of decks.	3.	
Number of masts.	2.	
Rigged.	None	
Form	Cruiser.	
Plating	Lapped Plating.	
Galvanizing	None	
Material	Cruiser.	
Framework and description of vessel	Steel (Ice Breaker) <i>Twin Sc</i>	
Number of bulkheads	7	
Number of water ballast tanks and their capacity in tons	14 (455 tons)	
Number of sets of Engines.	2 Vertical Triple Expansion.	
Manufacturers.	Vickers Ltd. Barrow-in-Furness.	
Particulars of Engines.	Cylinders 28 x 46 x 75/48 S. Nominal H.P. 284.17 I.H.P. 8,000. Speed 16 knots.	
Particulars of Boilers.	Scottish Marine. Number - 6. Pressure - 180 lbs. sq.in.	
Number of shafts.	2.	
Under deck tonnage.	2,106.99	
Gross tonnage.	3,269.02	
Register tonnage.	1,855.17	
Complement, Officers and men, and passengers.	256.	

Archibald Reid  
Surveyor to Lloyd's Register.



© 2021 *129k*

Hand No. 1 -  
Class 100 A1 -  
Owners Canadian  
Government



© 2021

Lloyd's Register  
Foundation