



Lloyd's Register of Shipping.

RECEIVED

Ocean Chambers, Lowgate,

29 AUG 1947

Hull, 28th August, 1947.

s.s. "REYKJANES".
ex "Empire Contay".

Dear Sir,

With reference to your letter of the 7th instant, respecting the above vessel, we beg to inform you in reply to your enquiries that :-

1. The spacing of the solid floors is 44 inches in way of Nos. 2, 3 and 4 Double Bottom Tanks, and 22 inches elsewhere, as shown on the approved Profile and Deck Plan.
2. The thickness of the tankside brackets is .30 inches.
3. The breadth at bottom of the bracket floors at the margin plate is 26 inches.
4. We have to confirm that the hatchways in the 2nd deck in way of the after hold are fitted with shifting beams and wood covers.

Yours faithfully,
The Surveyors.

Per:-

The Secretary,
LONDON.

Lloyd's Register
Foundation

Referred to the D.O.

For Ship Surveyors (F.E. Rpts.) to note.



© 2021

Lloyd's Register
Foundation