

Rpt. 13.

No. 9760

REPORT ON ELECTRIC FITTINGS.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL) 25 JUN 1927

Date of writing Report

19

When handed in at Local Office

24th June 1927 Port of Belfast

Received at London Office

No. in
Reg. Book.

Survey held at Belfast

Date, First Survey

6th May

Last Survey

6th June

1927

(Number of Visits)

on the

TWIN SCREW

LAGUNILLA

Tons

Gross

Net

Built at

Belfast

By whom built

Harland Wolff Ltd

Yard No.

792

When built

1927

Owners

Andrew Weir & Co.

Port belonging to

London

Electric Light Installation fitted by

Harland Wolff Ltd

Contract No.

When fitted 1927

System of Distribution

Two Wire Direct Current to Distribution Boxes

Pressure of supply for Lighting

110

volts, Heating

—

volts, Power

110

volts.

Direct or Alternating Current, Lighting

Direct

Power

Direct

If alternating current system, state frequency of periods per second

Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off

yes

Generators, do they comply with the requirements regarding overload

yes

, are they compound wound

yes

are they over compounded 5 per cent.

yes

, if not compound wound state distance between each generator

Where more than one generator is fitted are they arranged to run in parallel

No

, is an adjustable regulating resistance fitted in

series with each shunt field

No

Are all terminals accessible and clearly marked

yes

, are they so spaced or shielded that they cannot be accidentally earthed,

or short circuited

yes

Are the lubricating arrangements of the generators as per Rule

yes

Position of Generators

in Engine Room - Aft

is the ventilation in way of the generators satisfactory

yes

, are they clear of all inflammable material

yes

if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the generators

—

and

—

, are the generators protected from mechanical injury and damage from water, steam or oil

yes

are their axis of rotation fore and aft

yes

Earthing, are the bedplates and frames of the generating plant efficiently earthed

yes

are the prime movers and

their respective generators in metallic contact

yes

Main Switch Boards, where placed

in Engine Room on Aft Bulkhead

If the generators and main switchboard are not placed in the same compartment, is each generator provided with

a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard

—

Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes

yes

are they protected from mechanical injury and damage from water, steam or oil

yes

, if situated near unprotected

woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards

—

and

—

are they constructed wholly of durable, incombustible non-absorbent materials

yes

, is all insulation of high dielectric strength and of

permanently high insulation resistance

yes

, if semi-insulating material is used, are all conducting parts connected to one pole

insulated from the slab with mica or micanite and the slab similarly insulated from its framework

—

, and is the

frame effectively earthed

yes

Are the following fittings as per Rule, viz.:— spacing or shielding of live parts

yes

, accessibility of all parts

yes

, absence of fuses on back of board

yes

, proportion of omnibus

bars

yes

, individual fuses to voltmeter, pilot or earth lamp

yes

, connections of switches

yes

Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches

Each generator is connected to separate sets of bus-bars with double poles, switches & fuses, and each outgoing circuit has double-pole change over switches and double pole fuses

Instruments on main switchboard

two

ammeters

one

voltmeters

—

synchronising device for paralleling purposes.

Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system

Earth indicator

lamps with change-over switch to each set of bus-bars.

Switches, Circuit Breakers and Fusible Cut-outs, do these comply with the requirements of the Rules

yes

Section and Distribution Boards, is the construction, protection, insulation, material, and position of these as per rule

—



Lloyd's Register
Foundation

W1638-0210

2

Insulation of Cables, state type of cables, single or twin *single* are the cables insulated and protected as per Tables III or IV of the Rules *yes*
Fall of Pressure, state maximum between bus bars and any point of the installation under maximum load *5.0 Volts*

Cable Sockets and other connections, are the ends of all cables having a sectional area of 0.007 square inch and above provided with soldering sockets *yes*

Paper Insulated Cables, If cables are paper covered, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with insulating compound

Cable Runs, are the cables fixed as far as possible in accessible positions not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical damage *yes*

Support and Protection of Cables, state how the cables are supported and protected *cables are lead covered and passed through steel piping along decks.*

If cables are run in wood casings, are the casings and caps secured by screws *—*, are the cap screws of brass *—*, are the cables run in separate grooves *—*. If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VI *yes*

Refrigerated Chambers, if lights are fitted, are the cables and fittings in accordance with the special requirements *yes*

Joints in Cables, state if any, and how made, insulated, and protected *all joints are made in properly constructed junction boxes.*

Watertight Glands and Deck Tubes, are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands *yes*

Bushes in Beams and Non-watertight Positions, where unarmoured cables pass through beams and non-watertight partitions, are the holes efficiently bushed *yes*. state the material of which the bushes are made *Lead*

Earthing Connections, state what earthing connections are fitted and their respective sectional areas *All portable fittings, sockets etc., fitted other than to the steel work of the ship, are provided with an earthing connection equivalent to working conductor.* are their connections made as per Rule *yes*

Alternative Lighting, are the groups of lights in the propelling machinery space arranged as per Rule *yes*

Emergency Supply, state position and method of control of the emergency supply and how the generator is driven *yes*

Navigation Lamps, are these separately wired *yes*, controlled by separate switch and separate fuses *yes*

are the fuses double pole *yes*, are the switches and fuses grouped in a position accessible only to the officers on watch *yes*

has each navigation lamp an automatic indicator as per Rule *yes*, are separate screens provided for the use of oil and electric side lights *yes*

are separate oil lanterns provided for the mast head lights and side lights *yes*

Fittings, are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight *yes*

are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected

are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected *yes*

Special gas light fittings. how are the cables led

No. Main cables in the space - Branch circuits in lead covered steel armoured and braided clipped to steel work of ship. Passage in fore accommodation

Searchlight Lamps, No. of *—*, whether fixed or portable *—*, are their fittings as per Rule *—*

Arc Lamps, other than searchlight lamps, No. of *—*, are their live parts insulated from the frame or case *—*, are their fittings as per Rule *—*

Motors, are their working parts readily accessible *yes*, are the coils self-contained and readily removable for replacement *yes*

are the brushes, brush holders, terminals and lubricating arrangements as per Rule *yes*, are the motors placed in well-ventilated compartments in which inflammable gases cannot accumulate and clear of all inflammable material *yes*

are they protected from mechanical injury and damage from water, steam or oil *yes*

are their axis of rotation fore and aft *yes*

if situated near unprotected woodwork or other combustible material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type

if not of this type, state distance of the combustible material horizontally or vertically above the motors *—* and *—*

Control Gear and Resistances, are the generator field and motor speed regulators, starters and controllers constructed as per Rule *yes*

Lightning Conductors, where lightning conductors are required, are these fitted as per Rule *—*

Ships carrying Oil having a Flash Point less than 150° F. Have the special requirements of the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and fittings *yes*

If portable lamps for use in dangerous spaces are supplied, are they of a type approved by the Home Office *yes*

PARTICULARS OF GENERATING PLANT.

DESCRIPTION OF GENERATOR.	No. of	RATED AT				DRIVEN BY.	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE.	
		Kilowatts.	Volts.	Ampères.	Revs. per Min.		Fuel Used.	Flash Point of Fuel.
MAIN	2	5	110	45.5	650	8 B.H.P. single cylinder	—	—
AUXILIARY	—	—	—	—	—	3" dia x 12 1/2" stroke	—	—
EMERGENCY	—	—	—	—	—	Steam engine at 100 lbs per sq. in. steam pressure	—	—
ROTARY TRANSFORMER	—	—	—	—	—	—	—	—

LIGHTING AND HEATING CONDUCTORS.

Ref. No.	DESCRIPTION.	No. of Conductors.	Effective Area of each Conductor, Sq. Ins.	COMPOSITION OF STRAND.		Total Maximum Current, Ampères.	Approximate Length (Lead and Return), Feet.	Insulated with	HOW PROTECTED.
				No.	Diameter.				
—	MAIN GENERATOR	2	.0225	7	.064	45.5	30	Rubber	Lead covered
—	AUXILIARY GENERATOR	—	—	—	—	—	—	—	—
—	EMERGENCY GENERATOR	—	—	—	—	—	—	—	—
—	ROTARY TRANSFORMER	—	—	—	—	—	—	—	—
—	AUXILIARY SWITCHBOARDS	—	—	—	—	—	—	—	—
—	ENGINE ROOM	2	.003	3	.036	12.0	78	Rubber	Lead covered
—	BOILER ROOM	—	—	—	—	—	—	—	—
—	Off accom. & galley	2	.007	7	.036	20.5	104	Rubber	Lead covered
—	Flowers	—	—	—	—	—	—	—	—
—	Navigation & Wireless	2	.007	7	.036	9.07	520	Rubber	Lead covered
—	Food accommodation & Pump Room	2	.007	7	.036	13.3	448	Rubber	Lead covered
—	WIRELESS	2	.007	7	.036	2.27	496	Rubber	Lead covered
—	SEARCHLIGHT	—	—	—	—	—	—	—	—
—	MASTHEAD LIGHT	2	.003	3	.036	0.9	240	Rubber	Lead covered
—	SIDE LIGHTS	2	.003	3	.036	0.9	96	Rubber	Lead covered
—	COMPASS LIGHTS	2	.003	3	.036	0.36	56	Rubber	Lead covered
—	POOP LIGHTS	—	—	—	—	—	—	—	—
—	CARGO LIGHTS	3	.0048	110	.0076	1.36	200	Rubber	C.T.S.
—	ARC LAMPS	—	—	—	—	—	—	—	—
—	HEATERS	—	—	—	—	—	—	—	—

MOTOR CONDUCTORS.

Ref. No.	DESCRIPTION.	No. of Motors.	Effective Area of each Conductor, Sq. Ins.	COMPOSITION OF STRAND.		Total Maximum Current, Ampères.	Approximate Length (Lead and Return), Feet.	Insulated with	HOW PROTECTED.
				No.	Diameter.				
—	BALLAST PUMP	—	—	—	—	—	—	—	—
—	MAIN BILGE LINE PUMPS	—	—	—	—	—	—	—	—
—	GENERAL SERVICE PUMP	—	—	—	—	—	—	—	—
—	EMERGENCY BILGE PUMP	—	—	—	—	—	—	—	—
—	SANITARY PUMP	—	—	—	—	—	—	—	—
—	CIRC. SEA WATER PUMPS	—	—	—	—	—	—	—	—
—	CIRC. FRESH WATER PUMPS	—	—	—	—	—	—	—	—
—	AIR COMPRESSOR	—	—	—	—	—	—	—	—
—	FRESH WATER PUMP	—	—	—	—	—	—	—	—
—	ENGINE TURNING GEAR	—	—	—	—	—	—	—	—
—	ENGINE REVERSING GEAR	—	—	—	—	—	—	—	—
—	LUBRICATING OIL PUMPS	—	—	—	—	—	—	—	—
—	OIL FUEL TRANSFER PUMP	—	—	—	—	—	—	—	—
—	WINDLASS	—	—	—	—	—	—	—	—
—	WINCHES, FORWARD	—	—	—	—	—	—	—	—
—	WINCHES, AFT	—	—	—	—	—	—	—	—
—	STEERING GEAR	—	—	—	—	—	—	—	—
—	WORKSHOP MOTOR	—	—	—	—	—	—	—	—
—	VENTILATING FANS	—	—	—	—	—	—	—	—
—	Blower motor for galley range	2	.003	3	.036	5.6	75	Rubber	Lead covered
—	B.O. Machine	1	.007	7	.036	21	72	Rubber	Lead covered
—	Brine Pump	1	.003	3	.036	4	58	Rubber	Lead covered

All Conductors are of annealed copper conforming to British Standard Specification No. 7.

The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.

The foregoing is a correct description.

Electrical Engineers.

Date

16th June 1927

COMPASSES.

Distance between electric generators or motors and standard compass

208 feet

Distance between electric generators or motors and steering compass

203 feet

The nearest cables to the compasses are as follows:—

A cable carrying 9 Amperes 10 feet from standard compass 5 feet from steering compass.

A cable carrying 14 Amperes 22 feet from standard compass 14 feet from steering compass.

A cable carrying — Amperes — feet from standard compass — feet from steering compass.

Have the compasses been adjusted with and without the electric installation at work at full power

yes

Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted

yes

The maximum deviation due to electric currents was found to be Nil degrees on all course in the case of the standard compass, and Nil degrees on all course in the case of the steering compass.

Builder's Signature.

Date

16th June 1927

Is this installation a duplicate of a previous case

Yes

If so, state name of vessel

"Ambrosia"

General Remarks (State quality of workmanship, opinions as to class, &c.)

This installation has been fitted in accordance with the Society's rules. The materials and workmanship are good. It has been tried out under full working conditions. In my opinion the vessel is now eligible for notation "Electric light."

It is submitted that
this vessel is eligible for
THE RECORD. Elec. light.

Total Capacity of Generators 10 Kilowatts

The amount of Fee ... £ 10 : —

When applied for,

24 June 1927

Travelling Expenses (if any) £ :

When received,

2/8/27

Committee's Minute

TUES. 28 JUN 1927

Assigned

Electric light



© 2021

Lloyd's Register
Foundation