

COPY.

N1642-0239

now on way to Eng.

Lloyd's Register of Shipping,

71, Fenchurch Street, E.C.3.

19th November, 1937.

Enclosure.

Dear Sir,

(Y) 2
(Y). With reference to your letter of the 5th instant enclosing a generator test sheet which has been received from the Cleveland Surveyor in connection with the Yacht "MOANA", I have to point out that it would appear from the statement on the test sheet that no tests were taken on the particular generators intended for this yacht and the information relates to a similar machine of higher rating. While it is permissible to accept "type tests" as evidence of temperature rise it is required in all cases that the machines be run at the maker's works and that a high voltage insulation test be applied to all windings. During the run the compounding is to be taken and the figures obtained should be quoted on the test certificate.

It is stated on Cleveland Report No. 853 that the total capacity of the 2 sets is 100 kw. and the Westinghouse test sheet states that each generator is 60 kw.

In the circumstances I shall be glad if you will ascertain from the Surveyor which capacity is correct, and at the same time I return the test sheet for additional information to be furnished thereon.

W. Bennett, Esq.,
NEW YORK.

I am, Dear Sir,
Yours faithfully,

pro Secretary.