

W16H2 0248

11 NOV 1937

Yacht "MOANA".

IT IS SUBMITTED the generator test sheet be returned to the Surveyors for further information. It would appear from the statement on the test sheet that no tests were taken on the particular generators intended for this yacht and the information relates to a similar machine of higher rating.

While it is permissible to accept "type tests" as evidence of temperature rise it is required in all cases that the machines be run at the maker's works and that a high voltage insulation test be applied to all windings. During the run the compounding is to be taken and the figures obtained should be quoted on the test certificate.

Cleveland Report 853 states that the total capacity of the 2 sets is 100 kw. and the Westinghouse test sheet states that each generator is 60 kw. The Surveyors should state which is correct.

*L. S. W.*

15th November, 1937.



© 2020

Lloyd's Register  
Foundation