

COPY.

# Lloyd's Register of Shipping.

DURBAN

Port

29th May, 1954.



This is to certify that

P. F. BALFOUR

Designated Surveyor to this Society did at the request of

John T. Rennie & Sons, Lloyd's Agents at Durban, and the vessel "ATHELPRINCE", gross of Liverpool, on the 26th May, 1954, and subsequently, lay afloat in Durban Docks, in order to ascertain the nature and extent of damage stated to have been sustained through weather whilst on passage from Rotterdam - Durban direct, on 25th May, 1954.

Further particulars please see Log Books.

On examination the undersigned :-

FOUND

RECOMMENDED

BRING GEAR.

Hydraulic buffer gear bed plate holding down bolts (12) sheared. Three (3) wood blocks to which plate is secured, broken.

Holding down bolts to be renewed, and the three wood blocks to be renewed.


STARBOARD MAIN ENGINE DRIVEN WATER COOLING PUMP.

Pump cover fractured, due to engine racing. This cover had been previously cracked and repaired by brazing.

The cover to be renewed. This would have involved delay to the vessel, and therefore cover has been repaired by means of brazing. Flange face was found out of truth, and has now been faced up. Cover tested to 50 lbs. hydraulically prior to fitting.

/2

Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:-  
"While the Committees of the Society use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances whatever to be held responsible for any inaccuracy in any report or Certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its Committees or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."



M.V. "ATHELPRINCE".

FOUND

RECOMMENDED

It was recommended that a new cover be fitted on the vessel's return to the United Kingdom.

All the aforementioned recommendations have now been carried out satisfactorily.

(Signed) P.F. Balfour  
SURVEYOR TO LLOYD'S REGISTER  
OF SHIPPING.

Survey Fee £10.10.0.  
~~EXPENSES~~  
Expenses £1.1.0.



© 2021

Lloyd's Register  
Foundation

W1643-0040 (2/2)