

(LLOYD'S REGISTER.)

VESSELS OF 100 TONS AND UPWARDS.

G.R. 130.
Lloyd's Register.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.
(Signal Letters (if any)) **K.W.G.H.**

Official Number.		Name of Ship.		No., Date, and Port of Registry.	
149,865.		Beaconstreet.		130 in 1927.London.	
No., Date, and Port of Previous Registry (if any).					
Whether British or Foreign Built.	Whether a Sailing or Steam Ship ; and if a Steam Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.	
British	Steam Ship Single Screw.	Jarrow	1927	Palmer's Shipbuilding and Iron Company Limited Jarrow-on-Tyne.	
Number of DecksTwo	Length from fore part of stem, under the bowsprit, to the		Feet.	Tenths
Number of MastsTwo	aft side of the head of the stern post		450	3.0
RiggedSchooner	Length at quarter of depth from top of weather deck at			
SternElliptical	side amidships to bottom of keel		450	0.1
BuildClincher	Main breadth to outside of plank		59	7.0
GalleriesNone	Depth in hold from tonnage deck to ceiling at midships ...		34	0.5
HeadStraight	Depth in hold from upper deck to ceiling at midships, in the			
Framework and description of	Steel, Cargo	case of three decks and upwards		--	--
vessel	Depth from top of beam amidships to top of keel		34	2.5
Number of BulkheadsSeventeen	Depth from top of deck at side amidships to bottom of keel		34	5.2
Number of water ballast tanks,	Five	Round of beam		1	2.0
and their capacity in tons	1494 Tons	Length of engine room, if any		75	0.0

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel } 15950 Tons. | Ditto per inch immersion at same depth } 54.55 Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. B.H.P. I. H. P. Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.		
One	Triple Expansion Direct Acting Inverted Cylinder	Engines. British	Engines. 1927	Engines. Palmer's Shipbuilding and Iron Company Limited	Three 28"	51"		582
One	Particulars of Boilers.							
	Description.....Cylindrical Multitubular							
	Number.....Three							
	Iron or Steel.....Steel	British	1927	Jarrow-on-Tyne	46"	76"		3250
	Loaded Pressure.....180 lbs.							11 Knots

PARTICULARS OF TONNAGE.

GROSS TONNAGE.		No. of Tons.	DEDUCTIONS ALLOWED.		No. of Tons.
Under Tonnage Deck		6923.10	On account of space required for propelling power		2378.22
Space or spaces between Decks			On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew		193.94
Turret or Trunk			These spaces are the following, viz.:—		
Forecastle (Side Houses in)		10.66	Poop, Bridge & Round Houses		
Bridge space (Side Houses in)		27.36	(No. of Seamen or Apprentices for whom accommodation is certified 37)		
Poop or Break		160.44	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—		
Round		145.27	Masters Accommodation 22.25		
Side Houses			Boatswains Store 11.93		
Deck Houses		6.67	Wireless Telegraphy Room 3.08		
Chart House			Chart Space 6.67		
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894		158.43	Water Ballast Spaces 265.27		
Excess of Hatchways			Pump Spaces 36.76		
Gross Tonnage		7431.93	Total		345.96
Deductions, as per Contra		2918.12			
Register Tonnage		4513.81			2918.12

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 821.80 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 158.43 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Forecastle	L.43'	-	84.12 Tons
Bridge	L.32.7'	-	118.83 "
Poop	L.43.6'	-	144.26 "

Name of Master

Certificate of { Service No.
Competency No.


No. of Owners

Name, Residence, and Description of Managing Owner if there are more owners than one.

Beacon Transport Company of Canada Limited,
107, St. James Street,
Montreal, Canada.

Shares Sixty-four.

Dated 12th July, 1927.



Lloyd's Register
Foundation

W1647-0032

W1647-0034