

s.s. "ETNA".

No.69347 in the Register Book.

This vessel is not classed with this Society.

The Stettin Surveyors state that new engines of the "Lentz" Type are to be fitted in this vessel and they have been requested to survey the same during construction.

A plan of the crankshaft has also been forwarded for consideration.

IT IS SUBMITTED that with steam reciprocating engines of the "Lentz" Type for open sea service and having two H.P. cylinders each 420 mm. and two L.P. cylinders each 900 mm. dia. by 900 mm. stroke, working pressure 15 kg. per sq. cm., and with 4 cranks at right angles, the proposed size of crankshaft viz:- 285 mm. diameter merits approval, provided one or two keys or cylindrical dowels be fitted at the junction of the body pieces and webs. 9.5.27.


Return plan.

Retain copy.

[Handwritten signature]

[Handwritten signature]

L10/5/27



© 2019

Lloyd's Register
Foundation

W167-0102

RECEIVED ENDORSEMENT