

COPY.

# Lloyd's Register of Shipping,

71, Fenchurch Street, E.C.3.

Enclosure.

15th November 1937.

Dear Sirs,

E. I return herewith two copies of the plan, advised in your letter of the 6th instant, of small air receivers proposed for Messrs. Soc. Anon. John Cockerill's Yard No. 657, and with regard thereto I have to inform you that this plan, as shown and amended, will be approved for a working pressure of 25 ~~kg~~<sup>kg</sup> per sq.cm., provided the thickness of the dished-in end plate be not less than 12.6 mm., and the air receivers be constructed as Class 2 pressure vessels in accordance with the Society's Requirements for Welded Pressure Vessels intended for Land Purposes.

It is concluded the tensile strength of the material will be not less than 41 kg/mm<sup>2</sup>, but I shall be glad if you will confirm this point.

I have also to acknowledge the receipt of your letter of the 13th instant respecting this case and to confirm my cablegram of to-day reading as follows:-

"COCKERILL 657 AIR RECEIVER PLAN BEING RETURNED TONIGHT  
"SHOWING AMENDMENTS NECESSARY FOR APPROVAL".

I am, Dear Sirs,

Yours faithfully,

The Surveyors,  
ANTWERP.

Secretary.

W167-0184