


Messrs. Sir James Laing & Sons' Yard No. 721.

Plan shewing arrangement of portable plate on second deck, port and starboard, for withdrawing heater tubes submitted, in triplicate, by the Sunderland Surveyors.

It is submitted the Surveyors be informed that the scantlings and arrangements as shewn and amended will be approved, provided they be carried out to their satisfaction.

The Surveyors should be requested to inform the Builders that the bolted plate cannot be regarded as an integral part of the longitudinal strength, and doublings should therefore be fitted to compensate for the loss of effective sectional area of the deck plating.

*Pl. 1.10.37
Amnd. 4.10.37
2 plans
4 returned.*


4. 10. 37.



© 2019

Lloyd's Register
Foundation

W169-0044