

MEMORANDUM.

Messrs. A/B Ekensbergs Varv - Yard No.177.

Messrs. A/B Jönköpings Motorfabrik.

Auxiliary engine.

Plans Nos.11205, 11206 A,11207 & 141-372 R.

With 2 S.C.S.A. heavy oil engines for auxiliary purposes having 2 cylinders diameter of cylinders 170 mm., stroke 220 mm., span of main bearings 584 mm., maximum pressure in cylinders  $45 \text{ kg/cm}^2$ , M.E.P.  $3,21 \text{ kg/cm}^2$  and developing 50 B.H.P. at 700 R.P.M., the following sizes of crank shaft will be approved, viz:-

Pins ..... 130 mm. dia.

Journals ..... 110 mm. dia.

The details of the crank shaft, piston, connecting rod, and cylinder, as shown on the plans will also be approved.

GOTHENBURG.

19.4.40.



© 2020

Lloyd's Register  
Foundation

W170-0193