

MEMORANDUM.

Messrs. A/B EKENSBERGS VARV - YARD NO.177.

Messrs. Skandia-Verken A/B , Lysekil.

Auxiliary Engine.

Plans Nos.18-429 and 15-133.

With 4 S.C.S.A. heavy oil engines for auxiliary purposes having 2 cylinders, diameter of cylinders 170 mm., stroke 140 mm., span of main bearings 418 mm., M.I.P. 3.55 kg/cm², maximum pressure in cylinders 20 kg/cm², the following size of crank shaft will be approved, viz:-

Pins and Journals 80 mm. dia.

The details of crank shaft and connecting rod as shown on the plans will also be approved.

GOTHENBURG.

30.4.40.



© 2020

Lloyd's Register
Foundation

W170-0201