

COPY.

SHWR
ORDER NO. B 42927

30th November 1938.

The Ivor Speciality Co.Ltd.,
Ivor Works,
Kings Langley,
HERTS.

SHWR
by No.1606.

Our symbol No.7 B.

One La Mont exhaust gas boiler 4'1" int.dia.casing, heating surface 800 sq.ft. capable of evaporating 2,400 lbs. of steam per hour when supplied with 45,000 lbs. of exhaust gas per hour at a temperature of 675°F. Working steam pressure 120 lbs. per sq.inch, feed temperature 200°F. Main body of boiler casing to be lagged with 2" thick 85% magnesia slabs, covered with planished steel cleading. Complete with safety valve and in accordance with the specification detailed in yours of the 17th inst.

For your information we enclose herewith blue print No.B858A shewing arrangement of the main engine exhaust pipes.

Spare Gear our symbol No.Z 7 B.

One tube element of 4 layers.
2 Hand hole caps.
6 " " gaskets.
One set of control nozzles.

To Lloyds Survey and Norwegian Law requirements.

All nameplates etc. in Norwegian.

Early June 1939.



© 2019

Lloyd's Register
Foundation

W174-0176