

Messrs. Swan, Hunter & Wigham Richardson's Yard No. 1567.

-----  
and arrangement of webs  
Plan of forward deep tank submitted, / in triplicate,  
by the Builders direct.

It is submitted the Builders be informed that the scantlings and arrangements as shewn and amended will be approved, provided they be carried out to the satisfaction of the Society's Surveyors.

It is noted that this tank will be used for oil fuel in addition to vegetable oil or water ballast.

With regard to the proposal to weld the frame brackets to the tank top plating in the forward deep tank, the Surveyors should take an opportunity of discussing this matter with the Builders and pointing out to them that the attachment of the bracket will be concentrated on the tank top plating at a point in line with the floor below, whereas the attachment of that floor to the tank top plating will not coincide with the welded attachment. It is thought that in order to prevent any deformation and consequent damage owing to deformation of the plating between the line of the rivets and the line of welding, it would be advantageous to weld the heel of the bar to the tank top immediately below the proposed welding of the bracket.

Ltr. 7.11. Ansd. 15.11.  
P.C. & ltr. Nwc. 15.11.  
4 plans 2 retained



*AD*

© 2019  
15. 11. 38.

Lloyd's Register  
Foundation  
*AM*

W174-0258