

COPY.

Lloyd's Register of Shipping,

71, Fenchurch Street, E.C. 3.

23rd November, 1938.

Dear Sirs,

M.

I have to acknowledge the receipt of your letter of the 21st instant respecting Messrs. Aalborg Vaerft's Yard No. 64, and with regard thereto I have to inform you that the Owners' proposal to omit the side stringers in the holds in way of the strengthening for navigation in ice could be approved, provided the shell plating be increased .08" beyond the requirements of Section 40, para. 2(a) of the Rules, in association with an increase in the strength of the intermediate frames by 50% instead of 100% as proposed. Your suggestion, indicated in the last paragraph of your letter, is concurred in.

I am, Dear Sirs,

Yours faithfully,

The Surveyors,
COPENHAGEN.



Secretary.
© 2019

Lloyd's Register
Foundation

W175-0165