

Messrs. Aalborg Vaerft's No.64

It is submitted the Surveyors be informed that Owners' proposal to omit the side stringers in the holds in way of the strengthening for navigation in ice could be approved, provided the shell plating be increased .08" beyond the requirements of Section 40, para. 2(a) of the Rules, in association with an increase ⁱⁿ ~~for~~ the strength of the intermediate frames by 50% instead of 100% as proposed. The Surveyors' suggestion as indicated in the last paragraph of their letter is concurred in.

Ltr. 21/11. Ansd. 23/11



© 2019
23.11.38.

Lloyd's Register
Foundation

W175-0166