

on a passage Port Said / Fremantle / London, additional tween deck bulkheads

"HADLEIGH"

Rpt.Lon.

No.110744

Extension of W.T. Bulkheads.

Before the question of the extension of the watertight bulkheads to the Shelter deck receives the consideration of the Committee, the Surveyors should be informed the records in this Office show that the bulkhead on frame 92 below the 2nd deck is not watertight, and it would appear that on account of the cross bunker hatchway the 'tween deck bulkhead now fitted on frame 91 is not effective. Even if the bulkhead on frame 92 were watertight, the scuppers now fitted at the after end of No.2 'tween decks are not in a correct position, as they drain into the cross bunker and not into No.2 hold. It is not stated whether the existing scupper pipes, led from No.3 'tween decks into the after end of the machinery space, have been fitted with self-closing cocks as required in this case.

The Surveyors should be requested to furnish their remarks.

L. L. L.

T. O. CLOSED, W.H.F.

Lloyd's Register
Foundation

L.C.D.
26.11.42

GLASGOW.

W178-0047