

GLASS CONTEMPLATED.

(LLOYD'S REGISTER.)

G.R. 180.
Lloyd's Register.

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.
Signal Letters (if any) L.F.K.D.

Official Number.	Name of Ship.	No., Date, and Port of Registry.
161,349.	Hadleigh.	8 in 1930 London.

No., Date, and Port of Previous Registry (if any).

Whether British or Foreign Built.	Whether a Sailing Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steam Ship Single Screw.	Haverton Hill- on-Tees.	1929	Furness Shipbuilding Company Limited, Haverton Hill-on-Tees.

Number of Decks	One & open shelter	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post	Feet.	Tenths.
Number of Masts	Two	Length at quarter of depth from top of weather deck at side amidships to bottom of keel	406	3
Rigged	Schooner	Main breadth to outside of plank	404	8.1
Stern	Elliptical	Depth in hold from tonnage deck to ceiling at midships	56	0
Build	Clincher	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards	26	9
Galleries	None	Depth from top of beam amidships to top of keel	--	--
Lead	None	Depth from top of deck at side amidships to bottom of keel	29	4.1
Framework and description of vessel	Steel Cargo	Round of beam	29	6.3
Number of Bulkheads	Seven	Length of engine room, if any	1	1.3
Number of water ballast tanks, and their capacity in tons	Eight -1633.		49	8

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel 11277 Tons. Ditto per inch immersion at same depth 45.44 Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of Engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. B.H.P. I. H. P. Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.		
Three	Triple Expansion Inverted Direct Acting Surface Condensing	Engines.	Engines.	Engines.	Three			526.57
	Particulars of Boilers.	British	1929	Richardsons, Westgarth & Co., Ltd., Sunderland.	26"	48"	-----	-----
	Description.....Single Ended	Boilers.	Boilers	Boilers.	43"			2350
	Number.....three			Richardsons, Westgarth & Co., Ltd.	73"			
	Iron or Steel.....steel	British	1929	Hartlepool.				10½ knots
	Loaded Pressure.....200 lbs.							

PARTICULARS OF TONNAGE.

GROSS TONNAGE.		No. of Tons.	DEDUCTIONS ALLOWED.		No. of Tons.
Under Tonnage Deck		4819.45	On account of space required for propelling power		1671.02
Use in Shelter 'Tween Deck		39.95	On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew		
Fore or spaces between Decks		38.79	These spaces are the following, viz:— Poop and Round Houses (Number of Seamen or Apprentices for whom accommodation is certified.....).		244.48
Fore or Trunk		124.43	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—		
Forecastle Upper & Lower		194.34	Masters Accommodation 20.16		
Bridge space		4.97	Chart Space 4.97		
Poop or Break			Wireless 3.22		
Side Houses			Boatswain's Stores 52.22		
End Houses			Fore Peak Tank 42.40		
Chart House			After Peak Tank 31.90		
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894			Total ...		154.87
Excess of Hatchways			Cubic Metres		
Gross Tonnage		5221.93	14778.06		
Deductions, as per Contra		2070.37	5859.15		
Register Tonnage		3151.56	8918.91		2070.37

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 780.99 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 126.31 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Shelter Tween Decks Part 1.	Length	182.5'	-	725.67 tons.
" " " 2.	"	47.2'	+ 5.2'	160.61 "
" " " 3.	"	117.9'	-	521.69 "
" " " 4.	"	5.2'	-	21.65 "
Open Forecastle Length 23.1' + 6.7' x 2 + 2.3' x 2			-	46.47 "

Name of Master	Certificate of { Service No. Competency No.
No. of Owners	
Name, Residence, and Description of Managing Owner if there are more owners than one.	
The Atlantic Shipping & Trading Company Limited, 113-116, Bute Street, Cardiff.	The Rt. Hon. Baron Glanely of St. Fagans of same address -Manager-
Shares. Sixty-four.	
Dated 8th January, 1930.	