



WORKING PRESSURE 100 LBS PER SQ. IN.
 252 PLAIN TUBES 2 1/2" EXT. DIA. x 8 W.G. THICK, SWELLED 1/4" AT THE FRONT END.
 TENSILE STRENGTH OF SHELL PLATES 28 TO 32 TONS.
 SHELL TUBE PLATES 26 TO 30
 ALL OTHER PLATES 26 TO 30
 LAP WELDED IRON TUBES
 HEATING SURFACE 800 sq. ft. GRATE AREA 32 sq. ft.
 TO LLOYD'S SURVEY.

BLAKE PATENT BOILER 17'-3" HIGH x 8'-0" DIA. x 100 LBS.
 SCALE 1" = 1' FOOT

BOILER NO. 3183, 3269,



duplicate of approved plan
 J.M.
 9.6.14.

Blake Boiler, Wagon & Co. Ltd.

Boiler No. 3269

for

Messrs. Vrijk & Zonen
Holland.

100 lbs W.P.

No. 5410
LLOYD'S TEST
200 lbs.
23.10.14 J.K.

Mab Rpt

No. 8408

"Helena Margareta"
EX

SS LARENBURG

Rot. 9626



© 2019

Lloyd's Register
Foundation

W178-0096