

Urgent
Messrs. Bremer Vulkan Yard No.748.

Carrying Petroleum in Bulk.

Mr. Lowrie, representing the Owners,
called yesterday afternoon with reference to the lighting
and ventilating of the hospital which is located in the
centre castle space immediately adjacent to the oil tanks.

The Rules do not permit switches or open
type motors in tween deck and similar spaces.

Favourable consideration might be given
to the use of flameproof switches and fittings in this
instance.

by air mail
IT IS SUBMITTED the Hamburg Surveyors be
informed accordingly and that no exception might be taken
to the use of flameproof switches and lighting fittings
in the hospital. Also that an electric fan in the hospital
is not permissible but an arrangement whereby the fan is
located on the deck above and connected by trunking to the
cabin for blowing air into the latter might be accepted.

La 8/2
asw.
8th February, 1938.



Lloyd's Register
Foundation

W180-0022