

Messrs. Bremer Vulkan's Nos.748-750.

It is submitted the Bremen Surveyors be informed that, while it was noted that certain details of the strengthening of bottom forward were shown on the profile plan, these were not complete, and it was assumed that a plan of strengthening of bottom forward would be submitted in due course, as required on the plan of midship section. The Surveyors should arrange for this plan to be submitted, and ^{it} should include particulars of the extent of the increased thickness of plating on the bottom forward, and also cover the additional thickness required between frames 152 and 164 on account of the wider frame spacing.

It should also be pointed out that back bars are required to be fitted to the transverse frames on the bottom in No. 1 tank, or equivalent arrangements provided. These were not ^{shown} ~~shown~~ on the profile plan.

Dr. 11. 8. 37
Amnd. 17. 8. 37
P.C. Ham.


17. 8. 37.



© 2019

Lloyd's Register
Foundation

W180-0089