



# Lloyd's Register of Shipping.

3, Wilhadistrasse,

Bremen, 23rd November, 1936.

LLOYD'S REGISTER  
RECEIVED  
25 NOV 1936  
AMSD. 28.11.  
LONDON

Dear Sir,

Reference


M.

Having reference to your letter of the 10th instant regarding plan of midship section for Messrs. Bremer Vulkan's yard Nos. 748, 749 and 750, I beg to give you hereunder translation of a letter received from the Builders:-

We beg to remark that the enlarged beam knees, as amended on the plan of midship section and as required in your letter for the frames and longitudinal bulkheads are in our opinion too great, as the depth of the amended knees would be 5 times the depth of the beams. This proportion seems to be not normal and greater than required by the Rules for single deck vessels. Still less we can understand wherefore you require in every tank the two further enlarged beam knees having a depth of about 7 times the depth of the beams.

Further we beg to say that both longitudinal side girders in the centre tanks are to be reduced in height in way of the pump rooms at frames 86-90 and 132-136, with regard to the arrangement of the pumps. Therefore we propose, in maintenance of the same approved section, to carry out the girders 1200 x 18 mm. with a rider plate 500 x 18 mm. welded symmetrically on top of the vertical girder plate.

We would feel much obliged if you would reconsider the item about the knees and for approval



© 2019

Lloyd's Register  
Foundation

W 180-0133(112)



Bremer Vulkan yard Nos.

-2-

748-750.

of the proposed scantlings of the girders in the pump  
rooms.

-----

I shall feel obliged for being informed  
of your decision with regard to the above letter of  
Messrs. Bremer Vulkan.

I am, Dear Sir,

Yours faithfully,

*A. Carstensen*

The Secretary,

LONDON.



CE 1100 1238

© 2019

Lloyd's Register  
Foundation

W180-0133(212)

Returned to the Office of the Secretary



1510-0133512

Referred to the Chief Ship Surveyor,

*slb*

25 NOV 1936

LONDON.

The Secretary,

*A. B. B. B. B.*

Yours faithfully,

I am, Dear Sir,

Messrs. Bremer & Co.

of your decision with regard to the above letter of  
I shall feel obliged to be informed

Yours,

of the proposed arrangements of the directors in the bank

100-824

-5-



© 2010

Lloyd's Register  
Foundation