



NOTES

TANK 13'-0" OVER SHELL 3'-3 3/8" INS. DIA. APT 124
CU. FT. CAPACITY

BUILT TO MEET REQUIREMENTS OF AMERICAN
BUREAU OF SHIPPING, LLOYDS, & U.S. INSPECTION
SERVICE

TO BE MADE OF SEAMLESS STEEL HAVING 65000 TO
72000 LBS. PER SQ. IN. TENSILE STRENGTH AND TO
WITHSTAND A WORKING PRESS. OF 1000 LBS. PER
SQ. IN. TANK TO BE HYDRAULIC TESTED TO 2000
LBS. PER SQ. IN.

ALL HOLES TO BE DRILLED
HEADS & MANHOLE COVERS TO BE OF 65000 TO 72000 T.S. STEEL

APPROVED	DATE
AMER. BUREAU SHIPR	7-21-25
LLOYDS REGISTER	7-21-25
U.S.G. STEAMBOAT INS. SERVICE	8-5-25
STANDARD OIL CO., N.J.	8-7-25

TODD SHIPYARDS CORPORATION
TIETJEN AND LANG DRY DOCK CO. PLANT
HOBOKEN, N. J.

M/S J. A. MOFFETT JR.
H.P. AIR STORAGE TANK
TYPE.

DRAWN BY	W.B.W.	APPROVED BY	
CHECKED BY	MAC	SCALE	
TRADED BY	W.B.W.	DATE	7-16-25
DATE REVISED			
TRAC. No.	1-8-318		

LLOYDS REGISTER
W181-0157