

W182-00251

"M/V. JAGERSFONTEIN."Now done (Contd.).

machined, Springs renewed as necessary, refitted and tested oil tight under pressure.

For DBS (due 4.42).

Donkey boilers (2) opened up, examined throughout together with mountings, Safety valves, doors & fastenings, & all found in order. All Safety valves adjusted under steam as above.

All furnace brickwork renewed & minor repairs to mountings.

Oil burning installation examined & tested under working conditions & all found in good working order.

For Part C.S.

Examined:- Propellers, sea connections & fastenings
Main Engine - Port Nos 1, 4, Starboard Nos 3, 4, Cylinder liner, pistons, rod, valves, gears, covers.

Starboard forward auxiliary oil engine - No 5 cylinder liner (new), piston, cover, valves, gears, Connecting rod, top & bottom ends & crankpin.

All found or now placed in order.

Repairs (to & T). The above four main engine piston rods also of two spares, machined true.

New upper piston installed on spare piston assembly and remaining spare piston crown built up by welding and ground off to original contour. Piston rings renewed as necessary
Starb. forward auxiliary oil engine - No 5 cylinder liner renewed.

Also other minor repairs & adjustments effected.

Note the + RMC Survey which became due 5.42 - has not been dealt with at this time, the owners having ascertained that a refrigerated cargo would not be carried on the loaded voyage after leaving the dry docks, and accordingly desired to defer this Survey meanwhile.

From a general external examination the Refrigerated machinery and appliances appeared to be in good working order.

Cert B/S issued, Copy herewith

Note vessel now taken over by B.M.W.T on "bare boat" basis and a general condition Survey carried out on their behalf to which report please refer for fuller particulars.

Excluded
in
Rule

Spadocum
Notid

Sum
17.8.42

© 2019
Lloyd's Register
Foundation