

COPY

LLOYD'S REGISTER OF SHIPPING

MEIKAI BUILDING

No. 32, AKASHI MACHI,

KOBE, April 9th 1938.-



TELEGRAMS: "REGISTER" KOBE

TELEPHONE: 2530 SANNOMIYA

The Surveyors,
HONGKONG

M/S "JAVANESE PRINCE"
Plan of Exhaust Gas Boiler.

Dear Sirs,

In reply to your letter of the 26th March submitting for approval the above plan in quadruplicate, I have to inform you that the plan will be approved for the proposed working pressure of 45 lbs. per sq. inch, provided the stand-pipes and mounting pads riveted to the boiler shell be made of cast or forged steel or wrought iron, compensation be fitted in way of the stand-pipe as indicated on the plan, and the boiler be made under the usual conditions of survey and testing.

With reference to the positions of the manhole and stand-pipe, it is considered that the distance between these large openings should be increased as far as practicable.

Two copies of the approved plan are being returned to you under separate cover.

I am, Dear Sirs,
Yours faithfully,

C. Macpherson

SURVEYOR TO LLOYD'S REGISTER.

© 2019

Lloyd's Register
Foundation

W182-0167.1