

COPY.

Lloyd's Register of Shipping,

71, Fenchurch Street, E.C.3.

Enclosure

7th August, 1937.

Dear Sirs,

E. I return herewith one copy of the amended plan, forwarded with your letter of the 31st ultimo, of main Boilers, Contract No.933 proposed by The Wallsend Slipway & Eng.Co., for Messrs. Swan, Hunter & Wigham Richardson's Yard No.1555, and have to acquaint you that this plan will be approved for a working pressure of 220 lb. per sq. inch, provided nuts be fitted to six stay tubes at the wide water space at the front tube plate, one additional stay tube be fitted at the bottom row of each wing nest, and the position of the longitudinal through stay at the lower back end plate be amended as shown on the plan and the boilers be constructed under the usual conditions of survey and testing.

The Steel Testing Surveyors should be advised regarding the tensile strength of the shell plates, butt straps and girder plates, viz:- 29-33 tons per sq.inch.

I am, Dear Sirs,

Yours faithfully,

The Surveyors,
NEWCASTLE-ON-TYNE.



© 2020
Lloyd's Register
Foundation
Secretary.

W186-0259