

8 JUN 1942

Ship Surveyor..... Received from Chief Ship Surveyor.....

ME "LILANOVER" REPORT Nwc. No. 100385.

The Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

Assessment to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points set out in the endorsement."—Extract from Sub-Committee's Report, 24/5/92.)

The 1st S.S. No. 3 due 3,40 has been partly held.

A notation of 'Examined 3,41' valid for 12 months has been assigned.

25

A further GENERAL EXAMINATION has been commenced.

The class is subject to permanent repairs to internal connections in A.P. tank and to indented keel plates Nos. 1 & 2 from forward, Nos. 2,3,4 & 5 from aft and shell plates A.5 (p.s) being dealt with at the first opportunity also to (a bower anchor and 15 fathoms of chain cable being supplied).

Action had been deferred pending receipt of a report from the Newcastle Surveyors after collision.

o.7 No.

33 72

The NEWCASTLE Surveyors report (4,42) the vessel placed in dry dock, bottom coated and on account of damage through collision, (see London Report 110323) the rudder mainpiece arms and coupling bolts renewed and 2 beams repaired, and minor repairs effected.

Some bow plating, fore peak bulkhead, fore peak tank top, frames, panting stringers etc. (s.s) found indented or buckled.

Temporary repairs have been effected and the Surveyors recommend permanent repairs at the first convenient opportunity.

The GENERAL EXAMINATION has now been completed and the windlass cable lifters renewed and minor repairs effected.

The damaged counter plating and keel etc. continue efficient.

It is submitted the vessel appears worthy to remain as classed and to have record of docking survey 4,42 subject as recommended and to counter plating etc. (p.s) being permanently repaired at the first convenient opportunity and as above and that a notation of 'Examined 2,42' valid for 12 months be assigned as recommended.

As now,)
4,42 Shl.) Subject etc.
'Examined 2,42'

W189-0146

Lloyd's Register Foundation
8.6.42
S.S. PART HELD.