

Messrs. Wm. Hamilton's No. 440. Dimensions: 415' x 60.16' x 38.25'.

---


Plan of profile and deck submitted, in triplicate, by Messrs. Sir J.W. Isherwood & Co.

It is submitted that provided the arrangements be carried out as shewn and amended and to the satisfaction of the Society's Surveyors, they will be approved.

This vessel is of a length to require seven watertight bulkheads and while it is noted from the profile plan now submitted that it is proposed to fit this number of watertight bulkheads, two of those forming the boundaries of the deep tank are only 14 ft. apart and cannot be considered to comply with Section 7, Para. 2(a) of the Rules, which requires that watertight bulkheads must be fitted at a reasonable spacing.

It is therefore further submitted Messrs. Sir J.W. Isherwood be informed as above, and that the Special Survey during construction may be proceeded with, but before the vessel is finally classed in the Register Book it will be necessary for a letter to be furnished by the Owners agreeing to the spacing of the bulkheads as proposed, and if this be done a notation will be made in the Register Book in respect of the bulkheads as follows:

"1 intermediate BH dispensed with; 5BH to 2nd Dk;  
"collision BH to shelter dk".



16.6.39.

© 2019

Lloyd's Register  
Foundation

W192-0214