

MESSRS. WM. HAMILTON'S SHIP NO. 440.

EQUIPMENT NUMERAL.

$L \times (B + D) = 415 \times (57.87 + 38.25) = 39,890$  ✓

After Deckhouse =  $27 \times 7.5 \times .5$  ..... = 101.25 ✓  
Casings..... =  $69 \times 7.5 \times .5$  ..... = 258.75 ✓  
Saloon..... =  $28 \times 7.5 \times .5$  ..... = 105. ✓

40,355. = letter at

*Equipment letter increased  
to 40392 see Messrs. Johnson &  
letter 3/6/39*

EQUIPMENT.

3 Bower Anchors Stockless collective weight =  $194\frac{1}{2}$  cwts. ✓

1 Stream Anchor ex stock..... = 19 cwts. ✓

270 fathoms  $2\frac{5}{16}$ " stud Chain Cables or 2" Tayco cables. ✓

90 fathoms 5" Steel Wire Stream Line (6 x 12) ✓

120 fathoms  $4\frac{3}{4}$ " Steel Wire Towline (6 x 24) ✓

2 off at 90 fathoms  $2\frac{3}{4}$ " Steel Wire Hawser (6 x 12) ✓

2 off at 90 fathoms  $2\frac{1}{2}$ " Steel Wire Warps (6 x 12) ✓

W192-0237



© 2019

Lloyd's Register  
Foundation