





found satisfactory.

Stark Spars and Rigging examined, and found in order nothing removed. All leadings in berths and accommodation removed, and the plating exposed throughout also in way of all side lights, now recoated in good condition.

Pumps, Water tight doors, air & sounding pipes and general equipment examined found in order.

Steering gear overhauled, as well as blocks, guides & chains rods found in order.

Auctions compared with their certificates and cables ranged and also compared with the certificates on board found in order. Cables ranged found 563 Metres 60% Standard cable in order. Hoarsens complete.

Coca Nut Oil A. Deep tank has been filled in accordance with the approved plan dated 24.9.21. Tested as required by the Rules and found tight. Sparrow filled in the cargo hold bulkhead and drainage to Bilges

Length of Tank 33 ft. Water capacity 906 Tons

Insulation fitted in one hold in accordance with the approved plan. See Insulation Report.

L. P.

When Anchors or Cables are supplied, the particulars are to be reported in the following form:—

ANCHORS.

Number of Certificate.	Anchors.*	WEIGHT, EX. STOCK.			WEIGHT OF STOCK.			TEST, PER CERTIFICATE.			WEIGHT REQUIRED by TABLE 30 or 31.			Description of Anchor.	Makers.	Where and when tested and Superintendent.
		kg.	qrs.	lbs.	kg.	qrs.	lbs.	kg.	qrs.	lbs.	kg.	qrs.	lbs.			
4086	1st Bower	3572			3572			53,400			3575			Gunn, Sweden	Gunn	Magdeburg 20/11/19
5211	2nd "	3524			"			54,000			3570			"	Madagley	" 29.8.19
5212	3rd "	3530			"			54,000			3500			"	"	" " "
	Collective Weight.	10556									10575					H. Lang
5760	Stream	1149			Incl. Stock			18800			1206			Ordinary forst	Col. Houn	Magdeburg 29. Aug.
5161	Kedge	584			"			11200			"			"	Mannheim	" H. Lang

\* When a bower anchor is supplied it must be clearly stated whether it is a 1st, 2nd, or 3rd bower.

CHAIN CABLES.

Number of Certificate.	Length and size supplied.		Test per Certificate.		WEIGHT OF CHAIN CABLE.		Length and size per Table 30 or 31.		Description.	Makers of Cables.	When and where tested and Superintendent.
	Length.	Diam.	Statutory.	Breaking.	Supplied.	Per Table 30 or 31.	Length.	Diam.			
24046	281.5	60	102010	Kg	23104	Kg	metre	mm	60	Deutsche Maschinenfabrik Zabrze.	Duisburg 21 Feb 19
24100	282.61	"	1142900	Kg	23105	Kg	metre	mm			
	563.11	"			46209	Kg	metre	mm			
Iron Stream Chain or Steel Wire...											
5733	2	"	2190								
5734	3	"	2142								

L. P.

N.B.—If this Report is copied by Copying Press, especial care must be taken that the copying paper is not so much damped as to spread the ink, or to cause it to show through to the other side.