

of CARDIFF.

21st. MARCH 1921.

J. Petree.

Mr. H. Cambridge, representing H. M. Ministry of Shipping,
survey the Steel Screw Steamer

"MINNA HORN".

3431 tons gross, for the purpose of ascertaining the nature and
extent of damage stated to have been sustained through
collision with Steamer "PANAGHIS VERGOTTIS", at Cardiff on
4th. March 1921.

On examining the vessel when lying afloat in Queen
Alexandra Dock, Cardiff, on 14th. March 1921 and subsequently,
the undersigned found on port side forward in first strake
below main sheer, No.3. plate indented in two places, with
channel frame in way.

Recommended that one plate in first strake below
main sheer be relieved and faired in place also one channel
frame in way, that all adjacent riveting and caulking be
tested overhauled and renewed as necessary, that the sparring
on ship's side, also carpenter's bench and stores etc., in way
be removed as necessary for access and refitted together with
other disturbed work, and the repairs be suitably coated




Lloyd's Register
Foundation

W203-0162 1/2

inside and out on completion of the work.

The foregoing recommendations have been made and repairs completed to our satisfaction, in order to meet the requirements of classification.

A handwritten signature in dark ink, appearing to read "J. Petree", is written over a horizontal line. The signature is fluid and cursive.

SURVEYOR TO LLOYD'S REGISTER OF SHIPPING.



© 2019

Lloyd's Register
Foundation

W203-0162

2/2