

COPY.

Lloyd's Register of Shipping.



Port of CONSTANTZA

12th. January 1940.

This is to Certify that

JOHN RUMBLE

the undersigned Surveyor to this Society did at the request of

Messrs Watson & Youell, Ltd., Lloyd's Agents, and with the consent of the Master attend on board the steel screw "PEGASUS", 3597 tons gross of Hong-Kong, whilst the vessel was lying afloat at Constantza on the 12th January 1940 for the purpose of ascertaining the nature and extent of the damage stated to have been sustained when the steel screw "CHRYSSOROI", 379 tons gross of Piraeus, whilst proceeding alongside the oil basin at Constantza on the 12th January 1940, came into collision with the "PEGASUS" which, at the time, was lying alongside the quay.

For further particulars please see logbooks.

FOUND

No. 1 shell plate in the third strake below sheer on the starboard side found to have a small but deep indent with a fracture about two and a half inches long. The web frame in way slightly buckled.

RECOMMENDED

Indent to be faired in place and fracture to be electrically welded. The web frame to be faired in place.

As a temporary repair to enable the vessel to proceed on her voyage, two cement boxes have been fitted in the fore peak, one on each side of the web frame, and the fracture has also been plugged with wood wedges.

All removals necessary to carry out the foregoing recommendations to be afterwards replaced and made good with part new material if necessary. The vessel to be restored as far as practicable to the same good and efficient condition as before the alleged damage occurred.

John Rumble

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:-

"While the Committees of the Society use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances whatever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its Committees or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."