

COPY.

Lloyd's Register of Shipping.



Hamburg Report No. 22443

Port of Düsseldorf

16th September, 1936.

Order: 846/ V 39 041.

This is to Certify that

Franz Schnell
the undersigned Surveyor to this Society did at the request of Messrs. Weber & Ochsenfeld of Weidenau/Sieg test on the 14th September 1936 at their works.....6.033 kg Open Hearth Mild Steel Boiler Rivets, ordered by Messrs. Howaldtswerke A.G. of Kiel and destined for the Vessel No.756, Boiler Nos.1525 - 1527.

Results of tests.

Diameter	Tensile str. in kg.p.sq.mm	Elongation in 8xd
22mm	46,3	32,4%
25mm	45,0	31,0%
28mm	44,7	31,4%
34mm	45,1	34,6%
35,5mm	45,6	30,0%
36,5mm	43,3	34,5%

Crushing, flattening and bend tests good.

Samples selected from the finished rivets were found in every respect in accordance with the requirements of the Society.
Sulphur prints made in the presence of the undersigned were found to be satisfactory.

Identification marks: **LLOYD'S**

Advice note attached.

F. Schnell
SURVEYOR TO LLOYD'S REGISTER

Fees: RM. 20.--
Expenses: RM. 10.--
Total: RM. 30.--
Düsseldorf account No. 94605

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that :-
"While the Committees of the Society use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances whatever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its Committees or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."

