

Messrs. Howaldtswerke Yard No.756

Pumping Arrangement in
the Machinery Space.

IT IS SUBMITTED the plan of pumping arrangement in the machinery space merits approval, provided the arrangements be as shown and amended on the plan and the remaining requirements of Sections 20 and 34 of the Rules (1935-6) be complied with so far as they are applicable.

It should be pointed out that, as required by Section 34, Clause 6(c), pipes which are to be used for draining machinery spaces are to be entirely distinct from pipes which may be employed in filling or emptying spaces where water is carried. Accordingly, the suction from the after peak tank to the bilge pump should be led direct to a valve on the pump and not connected through the bilge distribution chest.

It is concluded that the fire pump and general service pump will not be used for boiler feeding, since these pumps are connected to the ^{OILY} bilge line. An L-ported cock should be fitted on the injector sea suction, as now indicated on the plan, in order to prevent the injector drawing from the bilges.

The Surveyors should be asked to state the purpose of the connection now marked "A" on the plan.

25/23/9

Return plan
Retain copy


G.R.B.
W.D.A.

© J.M.A.

Lloyd's Register
Foundation
23.9.36.

W21-0172