

COPY.

Lloyd's Register of Shipping,

71, Fenchurch Street, E.C. 3.

Enclosure.

4th March 1937.

Dear Sir,

Messrs. Howaldtswerke's Yard No.756

E.

I return herewith one copy of the plan, advised in your letter of the 26th ultimo, showing arrangement of lighting in the pump rooms of the above vessel, and I have to make the following comments:-

1. The tube EF welded to the underside of the main deck should be continued through the deck plate and welded on both sides of this plate.
2. The fitting shown CD should be welded in the same manner and made cylindrical in the lower portion.
3. No switches are permitted inside dangerous spaces. (See Section 15, Clause 6c).
4. The glycerine seal cannot be accepted, as its maintenance would not be dependable. The necessity for its use is not apparent.

I now await your further remarks in the matter.

I am, Dear Sir,

Yours faithfully,

Secretary.

A. Chisholm, Esq.,

HAMBURG.



© 2019

Lloyd's Register
Foundation

(1/2) W21-0190

Messrs. Howaldtswerke A.G., Yard No. 756.

IT IS SUBMITTED that the plan of the arrangement of lighting in the pump rooms be returned unstamped with the following comments:-

- (1) The tube EF welded to the underside of the main deck should be continued through the deck plate and welded on both sides of this plate.
- (2) The fitting shown CD should be welded in the same manner, and made cylindrical in the lower portion.
- (3) No switches are permitted inside dangerous spaces; see Section 15, Clause 6 (c).
- (4) The glycerine seal could not be accepted as its maintenance would be ^{undependable} ~~unreliable~~. The necessity for its use is not apparent.

Return plan unstamped.
Retain copy.

RIM
3rd March, 1937.

24/3/37

How



© 2019

Lloyd's Register
Foundation

(2/2) W21-0190