

W210-0183

5c.7.28.

30 JUL 1929

Received by Chief Ship Surveyor.....

Received from Chief Ship Surveyor.....

VESSEL'S NAME *St S* "PROTECTOR" Rpt. *2ms* No. *16444*

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/92.)

Nature of Survey *2nd S.S. No. 3.*

THICKNESSES OF PLATING ascertained by drilling, and comparison of same with the original thicknesses.

The thicknesses are in or an inch.

STRAKE.	AMIDSHIP.					FORWARD.					AFT.					REMARKS.
	Original Thick- ness.	Thickness by drilling.		Diminution if any.		Original Thick- ness.	Thickness by drilling.		Diminution if any.		Original Thick- ness.	Thickness by drilling.		Diminution if any.		
		Port.	Std.	Port.	Std.		Port.	Std.	Port.	Std.		Port.	Std.	Port.	Std.	
SPAR SHEER STRAKE																
Strake below.....																
MAIN SHEER STRAKE	7	7	7	-	-	6	5½	5½	½	½	6	5½	5½	½	½	
1st Strake below.....	6	5½	5½	½	½	5	5	5	-	-	5	5	5	-	-	
2nd " "	6	5½	5	½	1	5	5	5	-	-	5	5	5	-	-	
3rd " "																
4th " "																
5th " "																
6th " "																
7th " "																
8th " "																
9th " "																

Drillings at ends to be made in the vicinity of the peak bulkheads.

The Grimsby Surveyors report this vessel placed on a slipway and the requirements of the 2nd S.S. No.3, due 5,29, complied with.

The shell plating has been drilled with results as shewn above which are satisfactory.

The bottom has been cleaned and coated and repairs and renewals effected to deck, bulkheads, casings, etc. as found necessary and a bower anchor and 120 fathoms of chain cable supplied.

It is submitted the vessel appears worthy to remain as classed, with record of survey 7,29 and notation of S.S. Gms.2nd No.3-7,29, as as recommended.

100A1
7,29 Gms.
S.S. Gms. 2nd No.3-7,29.

29.7.29.

Lloyd's Register
Foundation