

4.1.44

Elt.

=====

LLOYDS REGISTER  
71 Fenchurchstreet  
LONDON E C 3

LINDHOLMEN 979 BELGIAN STEEL 21 CHARGES NOW TESTED STOP  
THIRTYSEVEN CHECK TENSILE TESTS TAKEN STOP SEVEN RESULTS  
ABOVE 41 KILOGRAMS STOP REMAINDER AVERAGE 37 FOR SIDE SHELL  
AND SECONDDDECK PLATING AND 38 POINT 1 FOR TOPSIDES AND  
SHELTER DECK STOP FRAMES GERMAN STEEL THREE TESTS 38.7  
40.0 47.9 STOP ALL EXTENSIONS GOOD AND AVERAGE EQUALS 30  
PERCENT STOP THIRTYEIGHT BEND TESTS ALL GOOD STOP PROPOSED  
STRENGTHENING MIDWAY BETWEEN HATCH AND SHIPS SIDES  
CONTINUOUS HORIZONTAL PLATE GIRDER 450 BY 15 MM BELOW  
SHELTER DECK BEAMS WITH INTERCOSTAL TO DECK EXTENDING  
OVER MIDSHIP HALF LENGTH AND BEYOND TO TWOTHIRDS LENGTH  
ABREAST HATCHES PLEASE CABLE REPLY

LLOYDS REGISTER

*To be 20 mm*

Tel.170280

Norra Hamngatan 6.



© 2019

Lloyd's Register  
Foundation

W211-0165