

Messrs. Furness Shipbuilding Co. Ltd. Yard Nos. 283 & 300.

Petroleum in Bulk.

IT IS SUBMITTED the Builders be informed that owing to the breathing which will occur due to alternate heating and cooling, it is necessary to prevent explosive vapour from the pump room entering the interior of the box, and ^{to ensure} that the breathing takes place to the air on deck. In these circumstances it is considered ventilating arrangements of the box to provide free access of air from the deck should be made. The nature and disposition of these arrangements ^{should} be such as would preclude the ingress of water.


It is agreed the radiating surface of the box is of ample capacity to dissipate the heat developed by the 150 watt lamp.

Advise and forward a copy of the Builder's letter of the 25th instant to the Sunderland Surveyors.

Lrs 30/6

J. J. [Signature]

29th June, 1938.



Lloyd's Register
Foundation

W215-0160