

6 MAR 1936

Received by Chief Ship Surveyor

Received from Chief Ship Surveyor

VESSEL NAME

"SILVERAY"

Rpt.

Ver.

No. 4165

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

"The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/92.

Nature of survey

The class is subject to indented shell plating on starboard side forward being dealt with at the first convenient opportunity.

A proposal to close the tonnage opening in the shelter deck is under discussion (see endorsement and plans attached).

The Vancouver Surveyors now report the vessel placed in dry dock, bottom cleaned and coated and on account of damage sustained during heavy weather, rudder pintles and gudgeons have been dealt with, doubling plates fitted to shell plates F3 port and starboard sides where fractured immediately abaft collision bulkhead, stringer brackets to fore peak bulkhead reriveted, doubling plates fitted to A strake plating port and starboard sides where fractured at butts (two each side), as per attached print, repairs effected to after bulkhead stiffeners of after deep tank, a number of rivets renewed and minor repairs carried out.

New outer plates, port and starboard, have been fitted.

Owing to damage by fire some electric wiring has been renewed and deck planking caulked.

The indented plating, as above, has been examined and a request by the Owners to have the condition regarding same removed merits in the Surveyors' opinion approval.

The Special Survey No. 3, due 7/37, has now been partly held.

It is submitted the vessel appears worthy to remain as P.T.O.

227-127-0006(1/2)

"SILVERAY"

-2-

classed with record of survey 1,36 without special condition.

100A1)
With freeboard) Without etc.
1,36 Ver.)

To complete the Survey - See Report.

(B)✓

The Surveyor should be informed that having regard to the prescriptions of Clause 10 (b) & (c) of the Rules, it is concluded that it is proposed to complete the Special Survey No.3 before the due date, but he should be requested to state if this is so.

*A word with
Supt. Sullivan*



© 2019

Lloyd's Register
Foundation

W217 -0006(212)