

M. V. "SILVERAY". - Electric Cables.

Extract from letter (dated 30. 9. 25.) from Mr. Badger  
to Mr. Carnaghan.

-----

Sunderland Report No. 29100 (Sunderland Forge &  
Engineering Co. Ltd.)

Lead covered, armoured and braided cables were run in  
iron troughs riveted to the top side of the upper deck,  
or carried on brackets as convenient. These troughs were  
coated with bitumastic solution and after the cables were  
laid the whole was coated with Stockholm tar as  
a further preservative against the action of sea water  
if any should enter the trough. The covers were  
securely fastened by means of  $\frac{1}{2}$  bolts.

-----



© 2019

Lloyd's Register  
Foundation

W 217 - 00 61