

AIR MAIL.  
**COPY.**

Lloyd's Register of Shipping,

71, Fenchurch Street, E.C.3.

BY AIR  
MAIL.

24th January, 1940.

Dear Sirs,

M.

I am in receipt of your letter of the 5th instant regarding the steamer "SUSANA", and in reply I have to inform you that if the lower deck in the forward holds of this vessel is removed, web frames, 30" deep, about six frame spaces apart, should be fitted extending from the inner bottom to the second deck.

I may add that at the level of the present deck a side stringer of the same depth as the web frames should be retained, and the existing hold pillars should be replaced by pillars about 5½" diameter.

I am, Dear Sirs,

Yours faithfully,

Secretary.

The Surveyors,

HONG KONG.



© 2019

Lloyd's Register  
Foundation

W220-0025