

WOKINGHAM

22 SEP 1941

Port of

Newcastle

8

September 1st 1941

REPORT ON MASTS, SPARS, AND RIGGING.

Dear Sirs

Having, in accordance with your instructions,

examined the Masts, Spars, Iron Work of same, and Rigging, of the

Name of Vessel) S/S War Mehtar lying at the Middle Docks

on the (Date of examination) September 1st 1941,

I have to report that I found Fore Rigging Port and Starboard Stranded, Fore Topmast Stay, Fore Topmast backstays, carried away. Starboard Main Rigging Stranded. N^o 3 Shroud in Port Main Rigging Stranded in Topmast Stay and Starboard Main Topmast backstay, Stranded. Recommend the renewal of the above and that N^o 1 and 2 Shrouds in the Port Main Rigging be cleaned of the lead service. Shrouds coated and preserved 10/11 up. Several Lower Shackles and Cover Screw Eyes in the Fore and Main Rigging, worn in the tips and broken up. Recommend Screws and Lower Shackles to be fixed made workable and repaired where necessary

Fee £

To the Surveyors,

Lloyd's Register of Shipping,

Lloyd's Register
Foundation

W228-0019