

MARCONIGRAM
CABLEGRAM

sent to the Surveyor_s at **GENOA**

Dated **17.9.24**

M Department.

TRANSLATION.

VOJVODA PUTNIK (Ship's name)

If lowest

AWLMU-EFDIW...deck dispensed with

EGGYJ-AXHAK...in the holds

it

EKSWO-EHBUH...will be necessary

to support

AWZEX-EGGYJ...side framing in the

AXHAK-EKUMB...holds with

deep

AWZIZ-ECVOF...webframes and

BAERV-EDFUV...Side stringers at

present lowest deck level and amend pillaring

adequately to support

AWOPS-EBTIW...upper deck.STOP

Present

ALZYL-EKSWO...freeboards will be

EGLUM-FLIHR...increased two

EFJUF-FISNE...feet half an inch

EFZIS-BALHI...if tonnage opening

EFKAB-AWOHI...fitted in shelter deck

EBTIW-EFZIS...STOP If

AXUTE-EHJON...plating of

AWOMB.....third deck

removed

ALZYL-EGLUM...freeboard increase

EKSWO-FILAS...will be eleven inches



© 2019

Lloyd's Register
Foundation

W228-0133