

S.S. "MAID OF ATHENS", No. 66347 R. B.

Owners..... The Byron Steam Ship Company.

THIS VESSEL is under survey at Sharpness with a view to classification, and the Bristol Surveyors now report upon the equipment of anchors and cables on board.

It is found that the equipment number is such in relation to the grade that the letter may be taken as "o".

As the weight of the Bower Anchors is only about 4 per cent below that required by the Rules it is submitted the same might be approved.

The Stream and Kedge Anchors are practically equivalent to the Rule requirements, but the stud chain cable is somewhat deficient.

It is submitted that provided an additional 45 fms. of 1-3/16" stud chain cable be placed on board, and the remainder of the equipment be in accordance with the requirements of the Rules for the letter "o", the same might be approved for the figure "1".

28.9.22

FRI. SEP. 20 1922

Approved  
Subject

Dr. 26. 9. 22  
Ans'd 29th.



© 2019

Lloyd's Register  
Foundation

W229-0163