

Dimensions of Ship per Register, Length 40.9 breadth 36¹/₂ depth 16.2 Moulded depth, ft. 25
FRAMING
COPY.

Lloyd's Register of Shipping.

71, Fenchurch Street, E.C. 3.

1st August, 1922.

Encl.

Dear Sirs,

With reference to your letter of the 26th ultimo forwarding a plan of the tail shaft of your s. s. "MAID OF ATHENS", I beg to acquaint you that with engines having cylinders 16.15/16", 27.9/16" and 43.5/16" diameter by 31¹/₂" stroke, and working pressure 185 lbs per square inch, the size of the screw shaft as fitted, viz. 10.13/32" diameter is in accordance with the requirements of the Society's Rules provided that if the shaft be fitted with a continuous liner the diameter of the propeller be not greater than 14' 0", or if the shaft be not so fitted the diameter of the propeller be not greater than 12' 10".


It is noted that a plan of the boilers has been handed to the Society's Surveyors at Bristol.

The plan forwarded is returned herewith.

I am, Dear Sirs,
Yours faithfully,

Secretary.

Messrs. The Byron Steamship Co. Ltd.,
Port of London Building,
Pepys Street,
Seething Lane, E.C.3.



© 2019

Lloyd's Register
Foundation

W229-0180

W229-0181