

S. S. "MAID OF ATHENS"

-----

IT IS SUBMITTED the Owners be informed that with engines having cylinders 16.15/16", 27.9/16" and 43.5/16" diameter by 31½" stroke, and working pressure 185 lbs per square inch, the size of the screw shaft as fitted, viz. 10.13/32" diameter is in accordance with the requirements of the Society's Rules provided that if the shaft be fitted with a continuous liner the diameter of the propeller be not greater than 14' 0", or if the shaft be not so fitted the diameter of the propeller be not greater than 12' 10".

-----

It is noted that a plan of the boilers has been handed to the Society's Surveyors at Bristol.

*The Bristol Surveyors should be advised.*

Return plan

*[Signature]*

31. 7. 22.

*[Signature]*

*Et. 1. 8. 22*



© 2019

Lloyd's Register Foundation

W229-0181