

Port of *Newcastle* 20
November 29 1941

REPORT ON MASTS, SPARS, AND RIGGING.

Dear Sirs

Having, in accordance with your instructions,
examined the Masts, Spars, Iron Work of same, and Rigging, of the
Vessel *S/S Aghios, Spyridon Lyng at the Stanhope Buoy*
the (Date of examination) *November 29 1941*,

I have to report that I found *Fore and Fore Topmast Stays*
portary fitted and in poor condition. N° 2 Shroud in
Port Fore Rigging, and Port Fore Topmast Backstay
ruined. Port and Starboard Main Topmast
backstays stranded. Recommend the renewal of
above, and that splice bearings be fitted on
shroud in the Starboard Fore Rigging and
N° 2 Shroud in the Port Main Rigging. screws
shackles of the renewed wires to be tried
in workable and repaired where necessary
re and Main Mast Wedges are not drawn

F. Pearson

£ : :
the Surveyors,
Lloyd's Register of Shipping,
Newcastle on Tyne



© 2021

Lloyd's Register
Foundation

Continued

Port of

Newcastle

November 29th 1941

REPORT ON MASTS, SPARS, AND RIGGING.

Dear Sirs

Having, in accordance with your instructions,

examined the Masts, Spars, Iron Work of same, and Rigging, of the

Name of Vessel)

S/s Aghios Spyridon, continued

the (Date of examination)

Nov 29th 1941,

I have to report that I found Fids of the Fore and Main
 Topmasts, strained. Fairlead sheaves
 broken up. Recommend the Topmasts to be
 lifted, and the Fids put out for examination
 Main Mast is doubled on the fore side
 below the Rigging Hoop. Plating in good
 condition, above and below the Doubler
 Masts, spars, other Rigging and Ironwork
 in good condition

£ : :

The Surveyors,

Lloyd's Register of Shipping,

Newcastle on Tyne

H. Pearson



© 2021

Lloyd's Register
Foundation

W232-0046 (2/2)