

COPY *for the Rpt 119561*

Lloyd's Register of Shipping,

Recd. 16.6.43



14 JUL 1943

Port OF LIVERPOOL.

12th July, 1943.

This is to Certify that

A.W. JACKSON.

the undersigned Surveyor to this Society did at the request of the Owners' Superintendent survey the S.S. "CITY OF VENICE", 8762 Tons Gross of Glasgow to ascertain and Report on Damage stated to have been caused by Ranging and Bumping alongside the "CITY OF NORWICH" at Algiers, in February, 1943.

Attended on the 17th May, 1943 and subsequently, the vessel being in Dry Dock at Birkenhead.

IND.

RECOMMENDED.

ALL STARBOARD SIDE
PLATES NUMBERED FROM AFT.

Strake. No.5 Plate corrugated
.11,12,15 and 16 Plates slightly
in on Lower Landing.

To be removed, faired & refitted.
To be faired in place.

Strake. No.5 Plate badly set in.
6 Plate slightly set in
10 Plate badly set in
.15 & 16 Plates set in

To be removed, faired & refitted.
To be faired in place.
To be renewed.
To be faired in place.

Strake. No.8 Plate set in between
mes.

To be removed, faired & refitted.

.10 & 14 plates set in between frames. To be released and faired in place.

Strake. No.9 plate set in between
mes.

To be released and faired in place.

.12 and 13 plate corrugated.

To be removed, faired and refitted.

Frames, Bulkhead Wing plate on deep tank, shell bar etc., to be dealt with as found necessary after removal of shell plates.

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:—

"While the Committees of the Society use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances whatever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its Committees or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."

2.

"CITY OF VENICE".

FOUND.

RECOMMENDED.

Deep tank to be filled and tested on completion of repairs.

All removals necessary to effect repairs to be dealt with and replaced as formerly.

New and disturbed work to be recoated.

The foregoing recommendations were made to place the vessel in the same good condition as she was in prior to the stated casualty.

The repairs have not been dealt with at this time.

FOR A.W. JACKSON.

S.B. Lumsden

SURVEYOR TO LLOYD'S REGISTER.



© 2020

Lloyd's Register
Foundation

W236-0003 2/2