



NOTE :-

ITEMS 13 TO 22 AND 24 TO 26 TO BE SHERADISED TO PROCESS SPEC 22120

ITEMS 11 & 12 TO BE BOLTED IN POSITION BEFORE SHIPPING AND STENCILLED WITH THE NUMBERS AND SIGNS SHOWN ON THE DRAWING.

ITEM 12 BOLTED ON TO ITEM 5 TO BE STENCILLED $\frac{18}{18}$

ITEM 12 BOLTED ON TO ITEM 7 TO BE STENCILLED $\frac{27}{27}$

ITEMS 1 TO 7 TO BE STENCILLED 'POSITIVE' OR 'NEGATIVE' AS PER DRAWING, LETTERS TO BE $\frac{1\frac{1}{2}}{1\frac{1}{2}}$ HIGH.

ITEMS 1 & 2 TO BE WRAPPED IN TWO SETS OF TWO STRAPS EACH, EACH SET BEING SEPARATE FROM THE OTHER, WRAPPING TO CONSIST OF :-

1 LAYER OF SILK MICA $\frac{1}{2}$ LAP.

1 LAYER OF EMPIRE TAPE $\frac{1}{2}$ LAP

1 LAYER OF TREATED TAPE $\frac{1}{2}$ LAP

FINISHED WITH GREY ENAMEL.

BE FINISHED

IN SITE.

Lloyd's Register
236-099777
