

Lloyd's Register of Shipping.

(Report on Machinery, No. _____ Port _____)

No. 20303. ENGINE FORGINGS OR CASTINGS.

I have to report that the Forgings or Castings, as herein described, manufactured by The Langley Forge Co. Ltd. of Langley Green for the Engines No. B.N.12 being constructed by The Wallsend P. Eng. Co. Ltd. of Wallsend on Tyne for the Ship No. 'City of Hankow', being built by _____ of _____

have been inspected by me as set forth below, and found to be, so far as can be seen, sound and free from defects. These have been despatched to _____

The words FORGINGS or CASTINGS should be struck out as may be required.

Mark on Forgings or Castings.

Lloyd's
No. 3161
R.W.F. 10/2/30.

R.W. Fawcett
Sheffield
26/2/30.

	CRANK SHAFT.	THRUST SHAFT.	INTERMEDIATE SHAFT.	TUBE SHAFT.
	FLYWHEEL SHAFT.			SCREW SHAFT.
Material* ...	Siemens Steel			
How made ...	Forged			
If Annealed ...	Yes.			
Dimensions, Forgings	Dia 15 3/4"			
Weight, Castings				
Progress on Inspection	Rough machined			
Tests on Standard Test Pieces.	T. 872. D.			
Tensile Test— Tons per square inch	28.0	30.0		
Extension per cent	35.0 2"	33.0 2"		
Cold Bending Test— Angle before fracture	180°	180°		
Dates when Inspected	6/2/30 to 10/2/30.			

PARTICULARS OF OTHER TESTS APPLIED TO CASTINGS:—

Fee (if any chargeable) £ 3 - 3 - 0

To be paid at Sheffield.

* If of wrought iron, state whether piled bars or scrap. If of steel, state whether made by the Open Hearth process.

